



The Quotation for ZJ70 Drilling Rig (USED)

No	Name	Type	Unit	Qty	Price (USD)	Remark
1	70 Derrick		set	1		Including overhead crane
2	70 base		set	1		Base height 10.5M
3	Derrick lifting rope		root	1		
4	Derrick rope	Diameter 38mm	meter	1200		
5	Diesel engine	12V190	platform	4		
6	Integrated parallel box		platform	1		Including connecting universal joint shaft
7	Well site distribution room	6M*2.5M	pic	1		Internally installed motor starter cabinet, mast lighting distribution cabinet, air conditioning
8	mud pump	F-1600	platform	1		
9	mud pump	F-1600	platform	1		
10	Winch * electromagnetic brake	JC-70B	platform	1		For fully sealed winch, gear shift with toothed clutch, chain oil pump spray lubrication, roll valve anti-collision device, maximum input power 1470KW, maximum fast rope tension 450KN, suitable for 38 diameter steel wire rope, equipped with JC70 electromagnetic eddy current brake
11	hydraulic clamp	YQ125	platform	1		
12	Hydraulic station	160	platform	1		



13	Hydraulic anchor head	18T	pic	2		
14	B-type pliers	9 5/8	pic	1		
15	500KW Ford generator set	GF-500	platform	1		Supporting pure new
16	Square drill rod	133MM	root	1		
17	Square core	133MM	set	1		Pillar pin heavy-duty square bushing
18	turntable	ZP375	pic	1		Rotary table: diameter 952.5MM, maximum load 5850KN
19	New pneumatic winch	XJFH-5/35	platform	2		
20	Traveling car * hook	YC450	set	1		
21	water tap	SL450	pic	1		
22	Single arm lifting ring	450T	pic	1		
23	Automatic pressure fan	7 m ³	platform	1		
24	Electric screw pressure fan	7 m ³	platform	2		
25	Main distribution cabinet	6M*2.5*2.8M	set	1		
26	Disc brake hydraulic station		set	1		
27	Driller's operation room		set	1		
28	Drill pipe discharge tripod	8.5M*0.6M	pic	6		Using 127 drill rods for machining
29	4-inch water hose	19M,6M,4,7M	root	3		1 water hose and 3 mud pipes



30	Gas source room * gas storage tank		set	1		Container processing, screw compressor fan
31	Generator Set	150KW	set	1		Well site lighting usage
32	Energy saving generator	800KW	platform	1		
33	Mud manifold	4 inches	set	1		2 sets of herringbone fittings, 2 sets of T-shaped fittings, including 4 4-inch gate valves
34	Driller's side room	6M*2.5M*2.6M	pic	1		Install electromagnetic brake distribution cabinet in the room, and install hydraulic station for hydraulic pliers on one end
35	Elevated oil tank	35m ³ *3m ³	pic	1		Including flow meter and oil pump
36	Storage tank	35	pic	1		
37	Drill pipe anchor channel	9M*1.6M	pic	2		
38	Derrick pipe rack	2.8M*4	pic	30		Using 127 drill rods for machining
49	Derrick small horse stool		pic	2		
40	Derrick horse stool		pic	1		
41	Mousehole	11.5M	root	1		
42	Big rope reel rope device		platform	1		
Drilling solid control system						
1	1 # Mud tank	10M*2.5M*2.35 M	Pic	1		1 vibrating screen, 1 degasser, and 1 agitator for canned packaging
2	2 # Mud Tank	10M*2.5M*2.35 M	Pic	1		Assembly of one desilter, one sand remover, two agitators, and two sets of 55KW sand pumps
3	3 # Mud Tank	10M*2.5M*2.35 M	Pic	1		Assemble 1 centrifuge and 2 sets of agitators



4	4 # Mud Tank	10M*2.5M*2.35 M	Pic	1		Assembly: 2 sets of agitators and 1 set of 55KW electric funnel
5	5 # Mud Tank	10M*2.5M*2.35 M	Pic	1		
6	6 # Mud Tank	10M*2.5M*2.35 M	Pic	1		Heavy slurry tank
7	Mud tank seat guard room	2.8*2.5M*1.5M	Pic	1		
8	Drug mixing tank	2M*2M*1.8M	Pic	1		Used for mixing mud with medicine, including 1 set of agitator
9	Centrifuge	GLW550*1070N	platform	1		Horizontal spiral settling centrifuge,
10	High frequency vibrating screen	2ZS4.2-280	platform	1		High frequency dual screen 1450r/Min
11	Desander	LCS250*2	platform	1		
12	Deaerator	ZCQ 1/4	platform	1		
13	Desilter	LNC100*10	platform	1		
14	Stirrer	WNJ200	platform	8		Mixer assembly with double-layer mixing impeller, 11KW explosion-proof motor
15	Production water tank (set)	120m ³	Pic	2		Note: The entire fixed control system is equipped with brand new explosion-proof lights and explosion-proof plugs
16	Domestic water tank	5m ³	Pic	1		
17	mud gas separator	1200MM	set	1		Including pipeline and igniter U-shaped bend
18	Exhaust pipeline	219*6M	root	8		
19	Remote ignition device		set	1		

Drilling tools



1	Elevator	245	Pic	2		
2	Elevator	127 Slope	Pic	2		250 tons
3	Elevator	140 casing	Pic	2		
4	Slip	Safety slip	Pic	1		
5	Slip	Drill collar slip	Pic	1		
6	Joint	411*410	Pic	2		
7	Joint	4A11*410	Pic	1		
8	Joint	4A10*430	Pic	1		
9	Joint	630*410	Pic	1		
10	Joint	630*4A10	Pic	1		
11	Drill bit box	8 1/2	Pic	2		
12	Teece	411	Pic	2		
13	lifting sub	411	root	4		
Well control system						
1	35-70 Double Ram Blowout Preventer	35-70MPa	set	1		Including four ways and two gate valves
2	Annular blowout preventer	35-70MPa	Pic	1		Including screws connecting to the double gate
3	Kill manifold	35-70MPa	set	1		



4	Choke Manifold	35-70MPa	set	1		
5	Throttling control box		set	1		Including hydraulic pipelines
6	640-6 remote control room		Pic	1		
7	Hydraulic pipeline		root	8		Pure New
8	Driller's console		set	1		1 set of gas containing tube bundle
9	S-bend		root	2		new
10	Internal control pipeline	Fire resistant pipeline 5 meters	root	2		new
11	Anti spray pipeline	8.5m	root	16		
Derrick displacement device						
1	New processing slide	3m*2.1m*	pic	24		The panel is processed with 40mm steel plate
2	New sales	50*185mm	root	128		Including double headed pins
3	New oil cylinder	500T	root	2		
4	New pipeline operation cabinet		set	1		4 hydraulic pipelines at a height of 15 meters and 2 pipelines at a height of 20 meters
5	pull rod		root	8		127 drill pipe processing
6	Claw device		set	2		
7	Cylinder pin	120*380mm	root	4		
Top drive						



	Top drive	500 T	Set	1		Includes all electrical appliances
Sandblasting and anti-corrosion treatment						
Assembly and debugging						
Amount (USD)					3,155,000	

Note:

- 1. This quotation is EXW, the quotation is valid for 30 days.**
- 2. Delivery date: 50 days after receiving the advance payment (without holidays)**
- 3. Terms of payment: TT PAYMENT (Within 3 days after the contract is signed, 60% advance payment will be made, and the remaining payment will be made before delivery.)**
- 4. If on-site assembly and commissioning are required, the cost will be calculated separately.**