HEAVYWEIGHT CHAMPION OF WOOD WASTE GRINDERS!




STUMPS
BRUSH
CEDAR BARK
DEMOLITION
YARD WASTE
R.R. TIES
POLES

Also: PAPER PLASTIC TIRES

- Unsurpassed Product Output and Quality End Product.
- Produces a Finished End Product Eliminating the Need for Secondary Grinders.
- Tolerant of Rocks, Concrete, Dirt and Metals.
- Unsurpassed Lowest Total Maintenance Cost.
- Design Quality and Craftsmanship that Sets New Standards.

5 MINUTE
 Set-Up Time



MAINTENANCE COST OF GRINDER ALONE:

> Between \$.15 - \$.25 per ton of processed material

OPERATING COST OF ROADMILL

(including fuel, parts, maintenance and operator) Between \$1.50 - \$1.75 per ton of processed material





Continental Biomass Industries

Manufacturers of Stationary and Portable Biomass Recovery Systems

> 22 Whittier Street, Newton, NH 03858 Tel. 603-382-0556 FAX 603-382-0557

ROADMILL SPECIFICATIONS

COMPONENTS:

CBI GRIZZLY MILL, 48 X 60

18,000 lbs. Solid Steel Rotor turning at 600 rpm, with 20, 50 lb. bolted on Strikers

ENGINE

750 HP Caterpillar Diesel

FEED CONVEYOR

60" x 25' 10' wide Loading Hopper Metal Detector with Operator Station

DISCHARGE CONVEYOR

54" x 30' Discharge Height: 15' for Trailer Loading Capability Hydraulically folded for Transporting

TRAILER

Custom Built, Extremely Rugged Hydraulic Outriggers Walking Suspension, 10' Axles

HYDRAULIC SYSTEM

Tank, Filter, Variable Displacement Pumps, all neatly plumbed using Stainless Tubing

V-BELT DRIVE TO MILL

500 GALLON FUEL TANK

ELECTRICAL SYSTEM

Simplistic Design for Low Maintenance

ALL COMPONENTS SHOT BLASTED, PRIMED AND PAINTED CBI YELLOW

Warranty: 1-5 Years

DIMENSIONS:

WEIGHT: 92,000 lbs.

LENGTH: 52' Transporting, 57' Operating
HEIGHT: 13'2" Transporting, 18'4" Operating

WIDTH: 10'2

PRODUCT OUTPUT:

Up to 100 ton per hour, depending on material to be processed.

END PRODUCT SIZE OPTIONS:

2" minus - 15" minus





The sooner you look at a CBI Roadmill . . . the sooner you'll stop looking at other wood waste grinders!